



भारतीय विज्ञान शिक्षा और अनुसंधान संस्थान, पुणे
INDIAN INSTITUTE OF SCIENCE EDUCATION AND RESEARCH PUNE
(शिक्षा मंत्रालय, भारत सरकार का एक स्वायत्त संस्थान)
(An Autonomous Institution of the Ministry of Education, Govt. of India)

IISER PUNE campus, Dr. Homi Bhaba Road, Pune-411 008.

आई.आई.एस.ई.आर पुणे परिसर, डॉ होमी भाबा रोड, पुणे-411 008

No: 54(2) /IISER/Pune/2023-24/ 21

Dated 20-02-2024

कोटेशन आमंत्रित करने की सूचना

NOTICE INVITING QUOTATION

निदेशक, आईआईएसईआर पुणे की ओर से अधोहस्ताक्षरी द्वारा सीपीडब्ल्यूडी, महाराष्ट्र राज्य पीडब्ल्यूडी, रेलवे और एमईएस में से किसी के साथ पंजीकृत अनुमोदित और पात्र ठेकेदारों से 08/03/2024 को अपराह्न 3.00 बजे तक नीचे उल्लिखित कार्य के लिए मुहरबंद कोटेशन आमंत्रित किए जाते हैं। विद्युत (बी एंड सी) कार्यों के लिए उपयुक्त श्रेणी में या विभिन्न प्रकार के पंपों की आपूर्ति, स्थापना परीक्षण, कमीशनिंग और रखरखाव के क्षेत्र में विशेष विशेषज्ञ एजेंसी। कोटेशन उसी दिन अपराह्न 3.30 बजे खोली जाएगी।

Sealed quotations are hereby invited by the undersigned on behalf of the Director, IISER Pune for the work mentioned below up to 3.00 PM on 08/03/2024 from approved and eligible contractors registered with anyone of CPWD, Maharashtra State PWD, Railways, and MES in appropriate category for electrical (B&C) works OR specialized expert agency in field of Supply, installation testing, commissioning and maintenance of Various Types of Pump. The quotations will be opened at 3.30 PM on the same day.

कार्य का नाम: आईआईएसईआर पुणे में विभिन्न प्रकार के जल पंपों की मरम्मत और पुनः स्थापना।

एजेंसी का नाम और पता :

Name of work: Repairing and Reinstallation of various types of water pumps at IISER Pune.

Name, address & e-mail of the agency –

नियम और शर्तें:

- आवेदक को विद्युत (बी एंड सी) कार्यों के लिए उपयुक्त श्रेणी में सीपीडब्ल्यूडी, महाराष्ट्र राज्य पीडब्ल्यूडी, रेलवे, एमईएस में से किसी के साथ पंजीकृत और पात्र ठेकेदार होना चाहिए या विभिन्न प्रकार के पंपों की आपूर्ति, स्थापना परीक्षण, कमीशनिंग और रखरखाव के क्षेत्र में विशेष विशेषज्ञ एजेंसी होना चाहिए। आवेदक को ग्राहक विभाग से पिछले तीन वर्षों के भीतर पूरे किए गए कार्य के अनुभव प्रमाण पत्र की प्रमाणित या नोटरीकृत प्रतियां कोटेशन के साथ पूर्णता प्रमाण पत्र की प्रति के साथ जमा करनी

Sign & Stamp of Agency



चाहिए। न्यूनतम पात्रता मानदंडों को पूरा नहीं करने वाले बोलीदाताओं को सरसरी तौर पर खारिज कर दिया जाएगा।

2. कोटेशन खोलने के बाद बैंक कार्य पूरा करने की समय अवधि IISER पुणे द्वारा कार्य आदेश देने की तिथि से 365 दिन होगी। आउट का कार्य ऐसी एजेंसियों को आईआईएसईआर पुणे के भविष्य के कोटेशन में भाग लेने से वंचित कर देगा। बोलीदाता maintenance@iiserpune.ac.in पर प्रश्न ई मेल कर सकते हैं- या उपरोक्त निर्दिष्ट कोटेशन की तारीख जमा करने से एक दिन पहले सभी कार्य दिवसों पर हार्ड कॉपी में आईआईएसईआर पुणे कार्यालय में जमा कर सकते हैं।
3. नोटिस आमंत्रण 121 दस्तावेज आईआईएसईआर पुणे से (एनआईक्यू, इंजीनियरिंग अनुभाग, मुख्य भवन, आईआईएसईआर पुणे परिसर, डॉ होमी भाभा रोड, पाषाण, पुणे 411008 -में सभी कार्य दिवसों से पहले सुबह 8 बजे के बीच प्राप्त किया जा सकता है। प्रस्तुत करने की तारीख। आवेदक 4 बजे से शाम 10 आईआईएसईआर पुणे की वेबसाइट <http://www.iiserpune.ac.in/links/tender-notice-and-eoi> से एनआईक्यू दस्तावेज प्राप्त करके कोटेशन जमा कर सकते हैं।
4. सभी एजेंसियों को 08/03/2024 को अपराह्न 3 बजे और उससे पहले सीलबंद लिफाफे में हार्ड कॉपी में अपना कोटेशन जमा करना होगा। ऊपर निर्दिष्ट तिथि और समय के बाद प्राप्त कोटेशन को स्वीकार नहीं किया जाएगा। किसी भी देरी, डाक देरी आदि पर विचार नहीं किया जाएगा। एजेंसी को सभी मदों के लिए कोट करना चाहिए बीओक्यू। शब्दों में उद्धृत दरों को एल1 बोली लगाने वाले के निर्णय के लिए अंतिम माना जाएगा। बोली मूल बोली दस्तावेज में प्रस्तुत किया जाना चाहिए (जैसा कि आईआईएसईआर, पुणे द्वारा जारी किया गया है या वेब कॉपी सुपर स्क्राइबिंग काम का नाम है। उद्धृत दरें कोटेशन खोलने की तारीख से 60 दिनों के लिए वैध होंगी। दरों को हाथ से लिखित रूप में उद्धृत किया जाएगा एनआईक्यू दस्तावेज में दिए गए स्थान।
5. कोटेशन उसी दिन अपराह्न 3 बजे एजेंसी या उनके अधिकृत प्रतिनिधियों 3.30, यदि कोई हो, की उपस्थिति में खोली जाएगी। एजेंसी का प्रस्ताव व्यावसायिक रूप से स्पष्ट होना चाहिए जिसमें एजेंसी द्वारा इस कोटेशन के सभी नियमों और शर्तों की स्वीकृति शामिल है। आईआईएसईआर पुणे बिना कोई कारण बताए कोटेशन को स्वीकार या अस्वीकार करने का अधिकार सुरक्षित रखता है
6. किसी भी शर्त के साथ जमा किए गए कोटेशन को सशर्त कोटेशन माना जाएगा और आईआईएसईआर पुणे द्वारा सरसरी तौर पर खारिज कर दिया जाएगा।
7. उद्धृत दरों में सभी सामग्रियों की लागत, श्रम लागत, जीएसटी, सभी कर, चुंगी, शुल्क, नमूने की लागत और प्रयोगशालाओं में सामग्री के परीक्षण के लिए शुल्क, रॉयल्टी आदि शामिल होना चाहिए। अतिरिक्त कुछ भी अलग से भुगतान नहीं किया जाएगा। नहीं, बोलीदाता अपनी बोली से संबंधित किसी भी मामले में बोली खोलने के समय से कार्य आदेश जारी करने के समय तक आईआईएसईआर, पुणे से संपर्क करेगा। बोलीदाता द्वारा आईआईएसईआर के बोली मूल्यांकन, बोली तुलना या अनुबंध पुरस्कार निर्णयों को प्रभावित करने के किसी भी प्रयास के परिणामस्वरूप उसकी बोली को अस्वीकार किया जा सकता है।
8. सभी स्वीकृत निर्माण बीओक्यू में निर्दिष्ट के अनुसार होंगे और सीपीडब्ल्यूडी विनिर्देशों के अनुसार, एजेंसी को तकनीकी डेटा डालना चाहिए और काम शुरू करने से पहले आईआईएसईआर पुणे की विभिन्न सामग्रियों के निर्माण पर पूर्व अनुमोदन प्राप्त करना चाहिए। सफल एजेंसी कार्य पूरा होने के मद्देनजर कार्य आदि के लिए सभी उपकरण और टैकल की अपनी व्यवस्था स्वयं करेगी। एजेंसी को एक स्रोत पर बिजली निःशुल्क उपलब्ध कराई जाएगी, एजेंसी को स्रोत से कार्य स्थल तक सुरक्षित रूप से बिजली के दोहन की व्यवस्था स्वयं करनी चाहिए। आईआईएसईआर पुणे द्वारा कोई अग्रिम भुगतान नहीं किया जाएगा। उद्धृत दरों में जीएसटी, टीडीएस और अन्य लागू कर शामिल होने चाहिए। काम के बिल से इनकम टैक्स और लेबर सेस की कटौती की जाएगी।



९. बीओक्यू नवीनतम सीपीडब्ल्यूडी विनिर्देश, आईएस विनिर्देशों और आईआईएसईआर पुणे के निर्देश के अनुसार जब भी सीपीडब्ल्यूडी आईएस विनिर्देश उपलब्ध नहीं हैं / के अनुसार किए जाने वाले कार्य के लिए विशिष्टता।
१०. ठेकेदार यह सुनिश्चित करेगा कि श्रमिकों और कर्मचारियों को श्रम कानूनों के अनुसार न्यूनतम मजदूरी का भुगतान किया जाए। सभी आवश्यक सुरक्षा उपकरणों आदि के साथ कार्य के निष्पादन के दौरान निर्धारित मानदंडों के अनुसार एल एजेंसी द्वारा मापी गई सभी सुरक्षा का पालन किया जाएगा। निष्पादन एजेंसी 1 व्यावसायिक रूप-सुरक्षा मानदंडों और संबद्ध मुआवजे आदि के सख्त पालन के लिए एकमात्र तकनीकी से जिम्मेदार होगी।
११. एजेंसी को काम पूरा होने के दिनों के भीतर भुगतान के लिए आईआईएसईआर पुणे को माप और 30 सार पत्रक प्रस्तुत करना चाहिए।
१२. एजेंसी को कार्य के निष्पादन के दौरान सभी सुरक्षा उपायों का पालन करना चाहिए, कोई भी दुर्घटना एजेंसी के दायरे में होगी।

Terms and Conditions:

1. The applicant should be approved and eligible contractors registered with anyone of CPWD, Maharashtra State PWD, Railways, MES in appropriate category for electrical (B&C) works OR specialized expert agency in field of specialized expert agency in field of Supply, installation testing, commissioning and maintenance of Various Types of Pump. Applicant should submit attested or notarized copies of the experience certificate for the work completed within last three years from client department with copy of completion certificate to along with the quotation. Bidders not meeting the minimum eligibility criteria shall be summarily rejected.
2. Time period for completion of work shall be **365 days** from the date of placing the work order by IISER Pune. The act of backing-out after opening of quotation will debar such agencies for participating in the future quotations of IISER PUNE. Bidder may e-mail queries on maintenance@iiserpune.ac.in or submit to IISER PUNE office in hard copy on all working days one day before submission date of quotation as specified above.
3. Notice Inviting Quotation (NIQ) document may be obtained from IISER PUNE at 121, Engineering Section, Main Building, IISER PUNE Campus, Dr. Homi Bhabha Road, Pashan, Pune - 411008 between 10 AM to 4 PM on all working days before date of submission. Applicant may submit quotation by obtaining NIQ document from IISER PUNE website at <http://www.iiserpune.ac.in/links/tender-notice-and-eoi>
4. All agencies need to submit their quotation in hard copy in sealed envelope on and before 3 PM on 08/03/2024. Quotation received after the date & time specified above shall not be accepted. Any delays, postal delay etc. will not be entertained. Agency should quote for all the items in the BOQ. Rates quoted in words shall be treated as Final for deciding L1 bidder. The bid shall be submitted in the original bid document (as issued by the IISER, Pune or Web copy super scribing the name of work. Quoted rates shall be valid for 60 days from the date of opening of quotations. Rates shall be quoted in hand writing at the spaces provided in NIQ document.
5. Quotations will be opened on the same day at 3.30 PM in the presence of agency or their authorized representatives, if any. The offer of the agency should be commercially clear

Sign & Stamp of Agency



including acceptance of all terms and conditions of this Quotation by the agency. IISER Pune reserves the right to accept or reject the quotation/s without assigning any reasons.

6. Quotations submitted with any conditions shall be treated as conditional quotations and shall be summarily be rejected by IISER PUNE.
7. Quoted rates should be inclusive of cost of all the materials, labour cost, GST, all taxes, octroi, duties, cost of sample and fees towards testing of materials in labs, royalties etc. complete. Nothing extra shall be paid separately. No, Bidder shall contact the IISER, Pune on any matter relating to his bid from the time of the bid opening to the time of issue of work order. Any effort by the Bidder to influence the IISER's bid evaluation, bid comparison or contract award decisions, may result in the rejection of his bid.
8. All approved makes shall be as specified in BOQ and as per CPWD specifications, agency should put-up technical data and obtain prior approval on makes of various materials of IISER PUNE before taking-up work. The successful agency shall make his own arrangement for all Tools & tackles for work etc complete in view of completion of work. Electricity shall be provided free of cost to agency at one source, agency should make own arrangement to safely tap of power from source to work location. No advance payment shall be made by IISER Pune. Quoted rates should be including GST, TDS and other applicable taxes. Income Tax and labour cess will be deducted from the bills of the work.
9. Specification for the work to be carried out as per BOQ, latest CPWD specification, IS specifications & as per instruction of IISER PUNE whenever specification CPWD/ IS specification are not available.
10. The contractor shall ensure that minimum wages should be paid to the labours and employees in accordance with labour laws. All the safety measures shall be followed by the L1 agency as per prescribed norms during execution of work with all the necessary safety tools etc. Executing Agency shall be sole techno-commercially responsible for the strict adherence of safety norms and allied compensations etc.
11. Agency should submit measurements and abstract sheets to IISER PUNE for the payments within 30 days from completion of work.
12. The agency should follow all safety measures during the execution of the work, any mishap happen will be responsibility of agency.


 अधीक्षण अभियंता
 आईआईएसईआर पुणे
 Superintending Engineer
 IISER Pune



Sign & Stamp of Agency

Date : 20/02/2024

Schedule of Quantity					
Name of work : Repairing and reinstallation of various types of water pumps at IISER Pune.					
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate(In words & Figures)(Including All Taxes)	Amount
A	B	C	D	E	F=CxE
1	Repairing of Crompton Greaves & Kirloskar make 20Hp 3Ph vertical Openwell Submersible pump set . Works includes replacement of copper winding , oil seal, motor brass bushing upper & lower set, set of bearing and its gaskets, rotor & impilear balancing, pump servicing, testing and installation with standard wire 3c x 4 sqmm copper flat cable with minimum 2 R x 3 meter in length . Trasportation for pump from IISER Pune to workshop & return, loading, unloading, labour, handling, taxes etc are included in scope of work for agency. (Warranty of minimum 6 months)	2	Nos		
2	Repairing of Crompton Greaves & Kirloskar make 15Hp 3Ph Openwell Submersible pump set . Works includes replacement of copper winding , oil seal, motor brass bushing upper & lower set, set of bearing and its gaskets, rotor & impilear balancing, pump servicing, testing and installation with standard wire 3c x 4 sqmm copper flat cable with minimum 2 R x 3 meter in length . Trasportation for pump from IISER Pune to workshop & return, loading, unloading, labour, handling, taxes etc are included in scope of work for agency. (Warranty of minimum 6 months)	8	Nos		
3	Repairing of Crompton Greaves & Kirloskar make 15Hp 3Ph Openwell Submersible pump set . Works includes replacement of empeler casing , oil seal, motor brass bushing upper & lower set, set of bearing and its gaskets, rotor & impilear balancing, pump servicing, testing and installation with standard wire 3c x 4 sqmm copper flat cable with minimum 2 R x 3 meter in length. Trasportation for pump from IISER Pune to workshop & return, loading, unloading, labour, handling, taxes etc are included in scope of work for agency. (Copper winding is not included for this item) (Warranty of minimum 6 months)	2	No.		



Schedule of Quantity					
Name of work : Repairing and reinstallation of various types of water pumps at IISER Pune.					
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate(In words & Figures)(Including All Taxes)	Amount
A	B	C	D	E	F=CxE
4	Repairing of Crompton Greaves & Kirloskar make 15Hp 3Ph Openwell Submersible pump set. Works includes replacement of oil seal, motor brass bushing upper & lower set, set of bearing and its gaskets, rotor & impeller balancing, pump servicing, testing and installation with standard wire 3c x 4 sqmm copper flat cable with minimum 2 R x 3 meter in length. Transportation for pump from IISER Pune to workshop & return, loading, unloading, labour, handling, taxes etc are included in scope of work for agency. (Copper winding & casing is not included for this item) (Warranty of minimum 6 months)	4	No.		
5	Repairing of Crompton Greaves & Kirloskar make 10Hp 3Ph Openwell Submersible pump set. Works includes replacement of copper winding, oil seal, motor brass bushing upper & lower set, set of bearing and its gaskets, rotor & impeller balancing, pump servicing, testing and installation with standard wire 3c x 4 sqmm copper flat cable with minimum 2 R x 3 meter in length. Transportation for pump from IISER Pune to workshop & return, loading, unloading, labour, handling, taxes etc are included in scope of work for agency. (Warranty of minimum 6 months)	2	No.		
6	Repairing of Crompton Greaves & Kirloskar make 15Hp 3Ph monoblock pump set. Works includes replacement of copper winding, oil seal, motor brass bushing upper & lower set, set of bearing and its gaskets, rotor & impeller balancing, pump servicing, testing and installation with standard wire 3c x 4 sqmm copper flat cable with minimum 2 R x 3 meter in length. Transportation for pump from IISER Pune to workshop & return, loading, unloading, labour, handling, taxes etc are included in scope of work for agency. (Warranty of minimum 6 months)	2	Nos		



Date : 20/02/2024

Schedule of Quantity					
Name of work : Repairing and reinstallation of various types of water pumps at IISER Pune.					
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate(In words & Figures)(Including All Taxes)	Amount
A	B	C	D	E	F=CxE
7	Repairing of 0.5Hp Pressure Booster pump set, which includes winding of motor, replacement of oil seal, bearing set, motor fan, pressure switch, pump servicing. Trasportation for pump from IISER Pune to workshop & return, loading, unloading, labour, handling, taxes etc are included in scope of work for agency. (Warranty of minimum 6 months)	2	Nos		
8	Repairing of 1 Hp Pressure Booster pump set, which includes winding of motor, replacement of oil seal, bearing set, motor fan, pressure switch, pump servicing. Trasportation for pump from IISER Pune to workshop & return, loading, unloading, labour, handling, taxes etc are included in scope of work for agency. (Warranty of minimum 6 months)	2	No.		
9	Repairing of 2 Hp 1Ph monoblock Mudpump pump set. Works includes replacement of copper winding, oil seal, motor bress bushing uppper & lower set, set of bearing and its gaskets, rotor & impleiar balancing, pump servicing, replacement of capacitor, testing and installation with standard wire 3c x 4 sqmm copper flat cable. Trasportation for pump from IISER Pune to workshop & return, loading, unloading, labour, handling, taxes etc are included in scope of work for agency.	1	No.		



Schedule of Quantity					
Name of work : Repairing and reinstallation of various types of water pumps at IISER Pune.					
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate(In words & Figures)(Including All Taxes)	Amount
A	B	C	D	E	F=CxE
10	Repairing of Crompton Greaves & Kirloskar make 5Hp 3Ph monoblock pump set. Works includes replacement of copper winding, oil seal, motor brass bushing upper & lower set, set of bearing and its gaskets, rotor & impeller balancing, pump servicing, testing and installation with standard wire 3c x 4 sqmm copper flat cable. Transportation for pump from IISER Pune to workshop & return, loading, unloading, labour, handling, taxes etc are included in scope of work for agency. (Warranty of minimum 6 months)	1	Nos		
11	Supply, installation, testing and commissioning of pressure switch make danfoss / L&T / Switzee Specification : Regulation range [bar] Pe: 2.00 - 14.00, Differential [bar]: 0.70 - 4.00, Reset function: Auto, Pressure connection type: Flare, Pressure connection size: 1/4, Enclosure rating IP: IP30, Max. Working Pressure [bar]: 17.0 with required accessories on existing pipe, as complete. (Warranty of minimum 6 months)	2	No.		
12	Supply, installation, testing and commissioning of Pressure gauge with 1/2" valve and accessories. specifications : Connection size 1/4 inch, Cabinet diameter 50, Measuring range (bar) 0 to 16, Scale division (bar) 0.5 bar, Connection location Below , Cabinet material Steel, Pressure gauge attachment Direct, Pressure unit bar/psi, Process connection material Brass. (Warranty of minimum 6 months)	2	No.		
13	Installation, testing and commissioning of existing pressure booster pump upto 1 HP, with accessories as required. Work includes supply and installation of required Gi pipe, 2 nos valve, NRV , bends , CPVC pipe , pipe connections, labour , required hardware etc . to complete the successful testing of booster pump. Required Starter, booster pump, pressure gauge and pressure switch will be provided by IISER Pune. (Warranty of minimum 6 months)	12	No.		



Date : 20/02/2024

Schedule of Quantity					
Name of work : Repairing and reinstallation of various types of water pumps at IISER Pune.					
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate(In words & Figures)(Including All Taxes)	Amount
A	B	C	D	E	F=CxE
14	Supply and laying of 3 C x 4 sqmm copper flat cable, 1.1 KV grade , PVC insulated , make Polycab/RR/Finolex (From pump to starter 2R x 10 m for each pump) (Warranty of minimum 6 months)	300	meter		
15	Supply and installation of pressure gauge 0-10 bar, 2" dia with required valve and Gi pipe connection as complete on existing water pipe line. (Warranty of minimum 6 months)	2	Nos		
16	Supply and laying of nylon rope of minimum 25 mm diameter in cross section : Single piece in length. (Warranty of minimum 6 months)	100	meter		



Date : 20/02/2024

Schedule of Quantity					
Name of work : Repairing and reinstallation of various types of water pumps at IISER Pune.					
Sl.No	Description of Work / Item(s)	No.of Qty	Units	Rate(In words & Figures)(Including All Taxes)	Amount
A	B	C	D	E	F=CxE
17	Supply and installation of 3" PVC footvalve with required accessories and hardware like clamps , nutbolts etc as complete. (Warranty of minimum 6 months)	2	Nos		
18	Supply and fixing of water proof joint on 3 c x 4 sqmm copper flat flax cable with all accessories , as complete. (Warranty of minimum 6 months)	24	Nos		
Total Amount in Words:				Total Rs.	

Note: Quoted Rate should be including all taxes/labour, transportation etc. Nothing extra shall be paid separately



[Signature]
Superintending Engineer
IISER Pune